Specification of Cold Room under Utility Facility

➢ Total Area: 200 Sq. Ft

➢ Equipment with Puff insulated pre-coated panel, Automated cooling control system, Temperature range: 3±1.C Tiled floor, Frost free cooling, Raised platform from ground