



Guwahati Biotech Park

**Amingaon, Kamrup Near SP Office
Guwahati- 781 031**

Ref: GBP/3.20.15 /2025-26/6082

Date: 17/10/2025

NOTICE INVITING QUOTATION FOR ALUMINIUM PARTITION WORK AT HONEY TESTING LAB OF GUWAHATI BIOTECH PARK

Guwahati Biotech Park invites sealed quotations from firm / agency having experience in interior work for execution of Aluminum partition work at Honey Testing laboratory of Guwahati Biotech Park, Amingaon. Details may be collected from the office of Guwahati Biotech Park or may be downloaded from the official website www.guwahatibiotechpark.com under Business/Tender section. Last date for submission of quotation is 23rd October 2025 at 2 PM.

Terms and Conditions:

1. Quotations will have to be submitted in a Sealed Envelope as per annexure -1 and should be addressed to The Chief Executive Officer, Guwahati Biotech Park, Amingaon, Kamrup, Guwahati -781031, Assam, India and reach the office of the Guwahati Biotech Park on or before 23rd October 2025 at 2 PM.
2. Before submitting the offer the bidder may visit the lab where the work is to be carried out.
3. Rates quoted should as per the format in Annexure I.
4. The selected firm will have to complete the work within 5 days from the date of issue of the work order.
5. Payment Terms:
 - a) 90% payment shall be made within 2-3 weeks from the date of successful completion of the work.
 - b) 10 % payment shall be retained as Security Deposit and will be released after Six months from the date of Completion.

Sd/

**Chief Executive Officer
Guwahati Biotech Park**

Annexure -1

Schedule of Rate

Ref: GBP/3.20.15 /2025-26/6082

Date: 17/10/2025

NAME OF THE WORK: ALUMINIUM PARTITION WORK AT HONEY TESTING LAB OF GUWAHATI BIOTECH PARK

SL NO	Description of Item	Qty	Rate in (Rs)	Amount in (Rs)
1	Providing and fixing aluminium Partition and Door work (Prelaminated particle board and glazing) with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete.	Sqm -99.81		
2	Dismantling of Brick work and finishing of the broken edge with cement plaster (1:4)	Sqm -2.6		
	Sub – Total (A)			
	GST @ on (A)			
	Grand Total			

(Rupees _____)

Bidder's Signature with seal